



C & I SYSTEMS

H-13(d), Electronic Complex,
 Road No. 1, I.P.I.A., KOTA-324005 (Raj.)
 Phone : 0744-2434994
 Mob. : +91-8003095306
 E-mail: civiltestinglab@gmail.com



ISO Certified

Civil Testing Certified Laboratory

Report No: - C & I/ 210525

Date: -06.03.2022

TEST REPORT

Name of Customer	RUBY CHILDREN SR SEC SCHOOL, BORKHANDI, BARAN ROAD, KOTA
Reference No.	Letter, Dated - 05.03.2022
Lab. Job No.	210525
Sample Receipt Date	05.03.2022
Name of Work	---
Material/ Material Identification	Water Sample
Make/Source	Drinking Water
Date of Testing	06.03.2022

TEST RESULTS

S.No.	Parameters	Results	Permissible Limits As per IS 10500- 2012(Max. Limits)	Test Method
1.	pH Value	6.90	6.5-8.5	IS-3025-P(11):1983
2.	Turbidity (NTU)	Nil	1.0	IS-3025-P(10):1982
3.	Taste	Agreeable	Agreeable	IS-3025-P(8):1984
4.	Colour	APHA	5	IS-3025-P(4):1987
5.	Odour	Agreeable	Agreeable	IS-3025-P(5):1983
6.	T.D.S.: (ppm)	150	500	IS-3025-P(16):1984
7.	Total Hardness (mg/lit.)	120	200	IS-3025-P(21):2009
8.	Acidity (mg/lit.)	6	---	IS-3025-P(22):1986
9.	Alkalinity (mg/lit.)	20	200	IS-3025-P(23):1986
10.	Chloride (mg/lit.)	27	250	IS-3025-P(32):1988
11.	Sulphate (mg/lit.)	30	200	IS-3025-P(24):1986
12.	Calcium (mg/lit.)	11.	75	IS-3025-P(40):1991
13.	Magnesium (mg/lit.)	8	30	IS-3025-P(46):1994

Checked by:



Authorized Signatory

Note: -

1. The test result refers only to the samples received in the Laboratory.
2. This report shall not be reproduced except in full without written approval from C&I SYSTEMS Laboratory.
3. Any discrepancy in test results should be reported within 15 days from the date of report.
4. C&I SYSTEMS Laboratory shall not in any way be involved in any action following the interpretation of test results.
5. This report is not valid any Legal proceeding.

End of Report
Page 1 of 1

Principal
 Ruby Children Sr. Sec. School
 Naya Nohra Kota